

TPC production

Igal Jaegle

University of Hawaii

for the Belle2 Collaboration

Mini-Group Meeting, 25th September 2015

Table of contents


- 1 Grounding implementation
- 2 TPC design: How the first four detectors differ

Grounding implementation

Wires AWG:

- LV PWR (3 wires) and GND (3 wires) => 22 AWG, conductor is smaller
- HitOR \pm (2 wires) => 24 AWG
- LVDS (8 wires) => 24 AWG

Grounding implemented as we agreed except for the wire AWG



Grounding implementation

Two vacuum LV wirings are done and the two others were about to be terminated with molex and ring lugs today

- If all 22 AWG switched to 20 AWG (with or without PTFE insulation), (one to two days) delays expected in the construction
 - ▶ All PEEK connectors must be re-done (really annoying)
 - ▶ Only PVC 18 or 22 AWG available in the LAB, **PVC outgassing a lot**
- Order ~ 100 USD of crimp contacts to replace the ones that will be used
- Order PTFE 20 AWG wires, 20 AWG with insulator or without?
- TPC shipment should be delayed by at least 2 or 3 days

TPC design: How the first four detectors differ

- Resistor type
 - ▶ Production resistors: MOX750F-100ME-ND
 - ▶ Prototype resistors: RNX100MBCT-ND
- FE orientation, 180° difference between production and prototype
- Prototype #2 will have a GEM spacer in Delrin instead of PEEK
- Possibly Prototype #2 might have a shorter drift gap but good hope 10cm might work, I will be sure only once HV test performed in He:CO₂

